

## Auditing Test Report

Test Report No.:SA13-4043/36

Date: 26/01/2023

### Client

Saudi Vitrified Clay Pipe Co.

P.O. Box 6415

Riyadh 11442

Kingdom of Saudi Arabia

Sampling Date: 22/01/2023

Test Date: 23/01/2023

### Auditing Purpose:

Testing of Vitrified Clay Pipes jointed by system C according to EN 295-1:2013

### Size Description:


Nominal Size: DN 600 \* 2000 mm  
Jointing System: System C  
Class: 160

### Description of Sampling

Samples were collected randomly from the stock at the client's manufacturing works in Riyadh (Kingdom of Saudi Arabia) by the agent of the Suhaimi - Fugro

### Underlying specification /description of the tests

EN 295-1:2013 "Vitrified clay pipe systems for drains and sewers - Part 1: Requirements for pipes, fittings & joints"  
GSO EN 295-1:2008 "Vitrified clay pipe systems for drains and sewers - Part 1: Requirements for pipes, fittings & joints"  
EN 295-2:2013 "Vitrified clay pipe systems for drains and sewers - Part 2: Evaluation of conformity and sampling"  
EN 295-3:2012 "Vitrified clay pipe systems for drains and sewers - Part 3: Test Methods"



## Test Results of DN 600 ES

Test Report No.:SA13-4043/36

Test Type		Unit	Sample 1	Sample 2	Sample 3	Req.	Result	
Pipes	Marking (visual Inspection)	-	✓	✓	✓	✓	✓	
	Crushing Strength	KN/m	119	125	120	≥ 96	✓	
	Internal Barrel Diameter "D1"	mm	605	602	605	≥ 585	✓	
	Length	mm	2000	2010	2010	2000 <sup>+4%</sup> <sub>-1%</sub>	✓	
	Water Tightness	L/m <sup>2</sup>	0.02	0.03	0.02	≤ 0.04	✓	
	Deviation from Straightness	mm	0.9	0.5	0.6	< 3.0	✓	
	Squareness of Ends	Socket	mm	6.2	6.8	6.6	< 12.0	✓
		Spigot	mm	6.2	5.6	6.7		
	Airtightness	mm	15	20	15	Drops ≤ 25	✓	
	Chemical Resistance	%	0.15	0.19	0.15	0.10-0.25%	✓	
Water Absorption	%	5.3	5.3	5.2	≤ 6 %	✓		
Joint Assembly	Joint Interchangeability (D4)	mm	758.3	758.3	758.4	758 ± 0.5	✓	
	Watertightness under Angular Deflection	0.5 bar	No leak, Deflection applied is 20 mm/m for 5 min.			No visible leakage	✓	
	Watertightness under Shear	0.5 bar	No leak, Shear force applied is 15.0 KN for 15 min.			No visible leakage	✓	
	Continuity of Invert	mm	3.6	3.7	3.9	≤ 6.0	✓	

*syed ham*

FUGRO - SUHAIMI LTD

Inam Syed

