

Auditing Test Report

Report No. SA13-4043/4

Date: 28/07/2022

Client

Saudi Vitrified Clay Pipe Co.

P.O. Box 6415

Riyadh 11442

Kingdom of Saudi Arabia

Sampling Date: 23/07/2022

Test Date: 24/07/2022

Auditing Purpose:

Testing of Perforated Vitrified Clay Pipes jointed by system C according to EN 295-5:2013

Size Description:

Nominal Size: DN 300 SS * 2000 mm Half Perforated

Jointing System: System C

Class: 160

Description of Sampling

Samples were collected randomly from the stock at the client's manufacturing works in Riyadh (Kingdom of Saudi Arabia) by the agent of the Suhaimi - Fugro

Underlying specification /description of the tests

EN 295-1:2013	"Vitrified clay pipe systems for drains and sewers - Part 1: Requirements for pipes, fittings & joints"
EN 295-5:2013	"Vitrified clay pipe systems for drains and sewers - Part 5: Requirements for pipes & fittings"
EN 295-2:2013	"Vitrified clay pipe systems for drains and sewers - Part 2: Evaluation of conformity and sampling"
EN 295-3:2012	"Vitrified clay pipe systems for drains and sewers - Part 3: Test Methods"



Test Results of DN 300 SS HP

Report No. SA13-4043/4

	Test Type	Unit	Sample 1	Sample 2	Sample 3	Req.	Result
Pipes	Marking (visual Inspection)	-	✓	✓	✓	✓	✓
	Crushing Strength	KN/m	56	57	58	≥ 55	✓
	Internal Barrel Diameter "D1"	mm	302	302	301	≥ 293	✓
	Length	mm	2005	2005	2015	2000 ^{+4%} _{-1%}	✓
	Perforation Area	mm ² /m	10215.2			≥ 900	✓
	Deviation from Straightness	mm	3.1	3.2	3.4	< 4.0	✓
	Water Absorption	%	3.2	3.5	3.2	≤ 6 %	✓
Joint Assembly	Joint Interchangeability	mm	371.4	371.2	371.3	371 ± 0.5	✓
	Continuity of Invert	mm	2.3	3.2	3.1	≤ 4	✓

FUGRO - SUHAIMI LTD

Mohammad Afaq

